



214 West Waldburg St

Scope of work:

Roof Replacement

Tear off and dispose of the existing shingle roof and related debris.

Furnish and install 1 layer of new Owens Corning synthetic felt directly to the entire roof deck.

Furnish and install new pre-painted edge metal around the perimeter of the house.

Furnish and install new ice and water-shield in all valleys, around the base of the chimney and around all roof penetrations.

Furnish and install new Owens Corning Starter Strip Plus shingles to both the eaves and the rakes.

Furnish and install new Owens Corning Duration Architectural shingles.

Furnish and install a new Owens Corning Vent-Sure ridge ventilation system. (40 FEET)

Furnish and install new Owens Corning Pro-Edge Hip & Ridge shingles.

Furnish and install new pipe boots and vents.

Install 6 nails per shingle to reach the 130-MPH wind warranty rating.

Replace the front porch roof with a 26ga Pre-painted 5V metal roof system.



Manufacturer's Specifications:

Owens Corning Duration Architectural Shingles - Quarry Gray
26ga Pre-painted 5V Metal Roof System - Old Town Gray

Physical samples of proposed materials:

Owens Corning Duration Architectural Shingles - Quarry Gray



Old Town Gray

26ga Pre-painted 5V Metal Roof System - Old Town Gray